



Federal Energy Regulatory Commission
Technical Conference on Connecticut Infrastructure

Reliability and Operability Committee
Update

Hartford, Connecticut
January 6, 2005

Stephen G. Whitley
Senior Vice President and Chief Operating Officer
ISO New England Inc.



Need for the 345 kV Loop

- Without the 345 kV Loop:
 - Bulk system reliability criteria cannot be met
 - Cascading blackouts could occur
 - System operators will need to resort to “pre-cautionary” load shedding to maintain overall grid stability



Inefficiency Costs of Existing Transmission System

- Estimated annual inefficiency costs for Connecticut (2005)
 - RMR Agreements: \$240 Million*
 - GAP RFP: \$33 Million
 - Congestion: \$4 Million
 - Running uneconomic generators: \$31 Million
 - Total: \$308 Million

* Includes agreements in effect and pending



Reliability and Operability Committee

- Committee Members:
 - ISO New England
 - Project Applicants: Connecticut Light and Power and United Illuminating
- Process:
 - ROC established: June 2004
 - Interim Reports: August 16, October 8
 - Final Report: December 20



Objective

- Determine maximum technological feasible use of 345 kV underground cable
- Meet operability and reliability requirements of the bulk power system in Southwest Connecticut and New England



Scope of Investigation

- An unprecedented amount of technical study conducted on this project due to:
 - Extreme weakness of the Southwest Connecticut system
 - Immediate and pending need for transmission upgrades
- Exhaustive technical analysis conducted
 - Harmonic frequency scans
 - Dynamic voltage analysis
- Multiple lengths of underground cable evaluated



Methods of Investigation

- World-wide experts employed
 - GE, PB Power, Shawnee Power, EnerNex, Teshmont, ABB, EPRI Solutions, and K & R Consulting
- Consulting team designed to work in parallel fashion
 - Engineers and consultants worked thousands of hours to complete necessary studies
 - Provide review of each others' work
 - Expedite study completion



General Findings

- As the length of underground cable increases, so do the variables that must be considered
 - Studies show high sensitivity to load levels, load types, amount of capacitance, etc.
 - Highly volatile and unpredictable results demonstrated
 - Operating in this manner is unprecedented world-wide
- Weakness of the Southwest Connecticut system limits the amount of underground cable that can be used
 - Voltage peaks/durations adversely impact existing system equipment
 - Ability to install new substation capacitor banks to solve local area problems



General Findings, cont.

- ROC has identified solutions that will work:
 - 4 linear miles of underground cable
 - 13 linear miles of underground cable
 - 24 linear miles of underground cable if mitigating measures employed
 - Substitute cable type (XLPE for HPFF) to reduce capacitance and harmonic effects
 - Extensive replacement of substation surge arresters and utilization of higher voltage rated equipment (circuit breakers rated 400 kV rather than 345 kV)
- Maximum use of 345 kV underground cable: 24 linear miles



Other Studies and Determinations

- KEMA
 - KEMA report in October suggested use of C-Type filters to mitigate harmonics issues and add undergrounding
 - Suggested further study to verify results
 - ROC conducted further study and determined C-Type filters help in some cases and hurt in others
 - KEMA approach would not be technologically feasible solution to add 345 kV underground cable



Other Studies and Determinations, cont.

- ABB
 - ABB proposed direct current (DC) project to be embedded in an alternating current (AC) system
 - ROC determined ABB approach would:
 - Not mitigate Southwest Connecticut reliability issues
 - Be a high risk, first of its kind multi-terminal “network” DC application
 - Result in unacceptable complexity
 - Cost nearly double and would be less likely to get any support for regional cost recovery
- The reasons above apply to the multi-terminal installation
 - Another option was for a less complex installation but it did not meet the project objectives



Next Steps

- Cost review for Bethel-Norwalk project (Phase I)
 - Regional vs. local allocation
 - NEPOOL Reliability Committee meeting February 2
 - Stakeholder meeting February 7
- Cost review for Middletown-Norwalk (Phase II)
 - Regional vs. local allocation
 - Stakeholder meetings to be scheduled upon receipt of cost application
- Reliability review of final Phase II design
 - NEPOOL Reliability Committee
 - ISO New England